

ADDENDUM #3

Project: Alterations and Expansion to the Lt. Job Lane Elementary School
TBA Project: 1258
Date: May 27, 2016

The attention of bidders submitting proposals for the above subject project is called to the following addendum to the specifications and drawings. The items set forth herein, whether of omission, addition, substitution, or clarifications are all to be included in and form a part of the proposal submitted.

THE NUMBER OF THIS ADDENDUM MUST BE ENTERED IN THE APPROPRIATE SPACE "B" PROVIDED AFTER THE WORD "No." ON PAGE "IB 14" OF THE CONTRACT FORM ENTITLED "FORMS FOR GENERAL BID" or AFTER THE WORD "No." ON PAGE "IB 27" OF THE CONTRACT FORM ENTITLED "FORM FOR SUB-BID"

Item 1. Q: The Finish Schedule indicates 'Tile Wainscot' in the following rooms; 103, 107, 108, 111, 111A, 205, 208 & 209. This wainscoting is not shown or detailed on the elevations, please indicate where this wainscoting is. If this is not detailed it will be understood that the only areas to get tile wainscot is at the stairs as shown on the elevations.

A: All existing corridors currently have a tile wainscot in the manner indicated on the revised schedules sheet A-6.0. New wainscots are installed as indicated on the finish schedule for new corridor areas and at corridor areas that are indicated for demolition. In no case is the wainscot tile to be set over existing tile wainscot that remains and is untouched by demolition. Corridors A, B, C, D all contain partial wall demolition and infill or modification and are to receive tile wainscot in areas indicated only. New corridor partitions in corridors F, G, H, and J are to receive new tile wainscoting. Partitions in these new corridor and corridor infill areas shall receive tile regardless of what the partition schedule indicates as a wallboard for that partition type.

Item 2. Q: Addendum #2 revises the comment to 'infill VCT', the revised demo plan from Addendum 2, D-1.1, still indicates that all flooring is to be removed, is this entire corridor to receive new VCT or just the area of the new angled wall?

A: The demolition plan indicates a shaded area in the corridor D and Janitor 207 where tile flooring is to be removed. Delete the note indicating the entire area of flooring is to be demolished. The proposed plan indicates the same area in corridor D and Janitor 207 where new VCT flooring is to be infilled. The demolition plan indicates that the flooring in the entire area of corridor B is to be removed. The proposed plan and finish schedule indicates that the entire area of corridor B is to receive new VCT flooring.

Item 3. Q: Some areas such as the Cafetorium 116, is not in the finish schedule, Storage 116 is in the finish schedule, but not shown on the finish plan. Are we to assume new VCT flooring in the Cafetorium?

A: Revise "Cafetorium 116" to read "Cafetorium 117A". The entire area of the cafetorium (less the existing stage) as noted on drawing D-1.1 (2910 sf) shall have the VCT flooring demolished. The entire areas of Cafetorium 117A and Cafetorium Addition 117 shall have new VCT flooring installed. VCT flooring shall be VCT #1, #2, and #5 as indicated on the finish schedule and in a scatter pattern as indicated elsewhere on the drawings. Storage 116 shall receive new VCT flooring throughout per the finish schedule.

Attachments:

None

Total number of pages of this addendum including attachments is one (1).

End of Addendum