

ADDENDUM #4

Project: Alterations and Expansion to the Lt. Job Lane Elementary School
TBA Project: 1258
Date: May 31, 2016

The attention of bidders submitting proposals for the above subject project is called to the following addendum to the specifications and drawings. The items set forth herein, whether of omission, addition, substitution, or clarifications are all to be included in and form a part of the proposal submitted.

THE NUMBER OF THIS ADDENDUM MUST BE ENTERED IN THE APPROPRIATE SPACE "B" PROVIDED AFTER THE WORD "No." ON PAGE "IB 14" OF THE CONTRACT FORM ENTITLED "FORMS FOR GENERAL BID" or AFTER THE WORD "No." ON PAGE "IB 27" OF THE CONTRACT FORM ENTITLED "FORM FOR SUB-BID"

Item 1. Q: Will specs be provided for the IT work?

A: The electrical contractor shall be responsible for the installation of the cables as indicated on the riser diagrams.

Item 2. Q: Will patch panels be required for the Data/Tel wiring?

A: If additional patch panels are required the school's IT group shall furnish and install.

Item 3. Q: Who owns the work of all of the data/tel termination and testing?

A: The school's IT group shall be responsible.

Item 4. Q: The drawings designate a light fixture type A1, however it is not indicated in the schedule.

A: The type "A1" lighting fixture shall be the same as the type "A" lighting fixture.

Item 5. Q: Note for exterior wall light in alt. #1 missing?

A: The installation of the type "E" lighting fixture above the door by the assistant principal office is to be included as part of the base bid in conjunction with the installation of the exterior door and steps. The door and this light are the only part of the work in the area labeled Alternate #1 to be included in the base bid.

Item 6. Q: Notes in the ceiling specs call for the removal of existing light fixtures. Is that correct.

A: The electrical contractor shall cut and make safe the disconnection of all existing circuits connecting fixtures to be removed. The general contractor shall be responsible for demolition of the ceilings and fixtures in the same. Electrical contractor shall be responsible for the installation of all new and reused fixtures and associated circuiting.

Item 7. Q: Section 09 51 20 Acoustical Tiles Ceiling, part 1.3.A: Delete the statement "2. Return of fixtures and ceiling mounted equipment for reinstallation of new or existing." Ceiling contractor shall coordinate their work with the other trades placing items or equipment in the ceiling.

Item 8. Q: 7. Drawing E-3.0 note 10 incomplete.

A: Note is complete.

Item 9. Q: Existing Switchboard Info: Please provide detailed information on the existing GE Switchboard. This info is needed in order for the E.C. to provide proper circuit breakers required in the existing Switchboard and to accurately bid this project. Manufacturer I Brand? Mode Number? Style I Series of circuit breakers?

A: The switchboard is a General Electric Spectra Series electric switchboard. Contractor should assume the circuit breakers have an "AIC" rating of 65,000 amperes.

Item 10. Clarification on D type light fixtures: The four "D" type fixtures at the cafetorium are existing wall hung pendant fixtures to be removed and reinstalled as ceiling mounted pendant fixtures in the new cafetorium addition space.

Item 11. Correct addendum number in the footer of Addendum #3 to read Addendum #3. Addendum #3 was issued as a single page on May 27, 2016.

Item 12. Clarification to specification attachments issued under addendum #2:
Replace Section 09 30 00 Tiling issued in the original bid documents with the revised Section 09 30 00 Tiling (10 pages) issued under addendum #2
Replace Section 14 42 16 Vertical Wheelchair Lift issued in the original bid documents with the revised Section 14 42 16 Vertical Wheelchair Lift (6 pages) issued under addendum #2.

Attachments:

None

Total number of pages of this addendum including attachments is two (2).

End of Addendum