Map by
Bedford
Public Works

Gate Valve
- New
- Remove and Replace
- To Remain
- Remove

Hydrant
- Remove and Replace
- To Remain

Water Main
- Clean and Line
- To Remain
- Service to Remain (services 1" or smaller not shown)

0 120 240 Feet

1 inch = 120 feet

N

Town of Bedford
Cleaning and Lining
March 2016

Page 2
Webber, Lane, Winthrop

GREAT RD

10" CLCI

CLEAN WATER MAIN
BACK TO GREAT ROAD

LIMIT OF WORK

FOR 175 GREAT ROAD:
NEW 6"x6" ANCHOR TEE
NEW 6" GATE VALVE
NEW 6" CLDI PIPE, APPROX. 20 FEET
NEW END CAP

2"

LOOMIS ST

FOR 3 LOOMIS STREET:
NEW 8"x6" ANCHOR TEE
NEW 6" GATE VALVE
NEW 6" CLDI PIPE,
APPROX. 10 FEET
NEW END CAP

8" CLCI

6" CI

LANE AVE

WEBBER AVE

WALSH RD

SEE PAGE 1

WINTHROP AVE

FOR WINTHROP AT LOOMIS
NEW 8"x6" ANCHOR TEE
NEW 6" GATE VALVE
NEW 6" CLDI PIPE, APPROX. 40 FEET
REMOVE EXISTING GATE VALVE
CLEAN BACK TO NEW GATE VALVE